

Lower Churchill Project

1 - Introduction and Project Components

June 2018

Boundless Energy



Privileged and Confidential in Contemplation of Litigation


Disclaimer

- This presentation was developed by consultants to the Lower Churchill Project team
- Any expressed opinions or other statements of what occurred in the project that are documented in the presentation are the product of the consultants' recollection
- The consultants have prepared a more comprehensive document addressing the project phases
- Any reliance upon or decisions made from the information that is contained in this presentation or the more detailed documentation prepared by the consultants is the sole judgement/decision of the user of the information
- In the event of any discrepancies between this presentation and other documentation, please contact the presenters for clarification

Take a **MOMENT** for Safety

Safety Performance

- ~ 43.0M hours worked project wide (End June 2018)
- **Zero fatalities**
- Multiple work fronts
- Harsh working locations
- Multiple contractors with varied safety procedures/processes
- 16 lost-time injuries
- ~10.3M hours worked with no LTI



Introduction

Introduction to the consultants

- Paul Harrington
- Ron Power
- Lance Clarke
- Scott O'Brien
- Pat Hussey
- Jason Kean

Objective

- Share accurate and relevant information and insights to assist Muskrat Falls Inquiry Counsel
- Present from a viewpoint and insight that few individuals hold (depth and breadth of knowledge of, and experience) with the Muskrat Falls Project ('MFP')
- Demonstrate a willingness to support the Commissioner's mandate and objectives related to the Muskrat Falls Inquiry

The scope of the presentation is from pre-sanction to date

1. Introduction and project components
2. Governance, oversight and assurance reviews
3. Project delivery model and organization
4. SNC-Lavalin contract
5. Contracting strategy and process
6. Astaldi contract
7. Pre-sanction
8. The sanction decision
9. Financial close / completion guarantees / COREA
10. Post-sanction
11. SNC risk report
12. Cost updates and forecasting

Key points of context

Inquiry context


- Our understanding
 - Making the best decision with the information available at the time (reasonableness at the time - not the 20/20 perfection of hindsight)
 - Fact based, no conjecture or “what if’s”
 - Materiality is critical
- Our perspective - the project is...
 - Extremely well documented – procedures and decisions
 - Heavily reviewed and scrutinized
 - Highly politicized and target of the media – led to a lot of misinformation, innuendo and false accusation
 - Expected ~95% complete at Sanction completion date (mid-2018)

Key points of context (cont.)

Industry Benchmarks


- Mega Projects experience a lot of challenges – many times due to strategic risk
- A 2016 McKinsey report highlighted:
 - Muskrat Falls is better than average on cost overruns (against P50)
 - Right on average for time overrun (much less than P50)
- For generation the capital \$/TWh for Muskrat Falls puts us right in the middle of the pack for recent Canadian Utility Mega Projects, cheaper than both Site C and Keeyask which have a lot of risk remaining

2016 McKinsey report: Cost and schedule overruns within construction industry



Comparison of capital efficiency (excl. IDC) for Muskrat Falls Generation to other generation projects

Approximate Costs per TwH (\$B/TwH)



Note: TwH = TerawattHour


Overview of components

General

Historical context

- In 2006 the Government of NL announced that Newfoundland Hydro (now Nalcor) would lead the development of the Lower Churchill Project
- A Provincial Energy Plan was developed in 2007 / 2008 which set the policy for all energy development in NL
- Nalcor was formed in 2008 to lead the implementation of this Plan

Nalcor's vision: *"to build a strong economic future for successive generations of Newfoundlanders and Labradorians"*




Phase 1 – Muskrat Falls

Phase 2 – Gull Island

Overview of components


Generating Site

Muskrat Falls Project




Muskrat Falls Generating Facility


Muskrat Falls Generating Facility



Layout verified by scaled operational model



Powerhouse overview



- Powerhouse will house the four turbines and generate up to 824 MW of power
- ~85 m high
- 4 Kaplan units
- The units at Muskrat Falls will be some of the largest and most efficient Kaplans in the world

The powerhouse



Construction takes place in harsh environments

Ice buildup



Ice buildup



Winter Construction



Night Shift




Intake and tailrace

Intake



Tailrace



Overview of components

Turbines and generators and Hydro-Mechanical Equipment (Gates and Hoists)

Heavy steel is manufactured in China

Forgings



Forgings



Turbine Stayring Fabrication



Machining



The heavy steel fabrication work was executed in China while the electrical and some specialized components are manufactured in other parts of the world

Some manufacturing was also done in India


Witnessing of rotor pole testing




Witnessing of rotor pole testing



Operational and schedule risk reduction Turbine Model Testing



Scroll Case



Runner Model (Diameter = 0.380m)

Draft Tube

Turbine equipment

Turbines equipment



Draft tube liner




Draft tube liner



Unit 1 – Staying Installation



Unit 1 - Draft Tube Liner Inplace



Some hydro-mechanical equipment was manufactured in different international locations


Manufactured in China



Manufactured in Germany



Trash Rack Cleaner




Overview of components

Spillway

Spillway



Aerial View



Overview of components

North Dam

North Dam – largest Roller Compacted Concrete (RCC) Dam in Canada



Overview of components


North Spur

North spur

North Spur aerial view




North Spur design



North spur construction


Early Days



Mid - Construction



Upstream Completed




Downstream Completed



Overview of components

Transmission Lines

Muskrat Falls Project



The transmission project scope

Scope summary

AC Transmission (Muskrat to Churchill Falls)

- ~ 265 km of two parallel 315 kV AC Transmission Line (TL), Muskrat Falls (MF) to Churchill Falls (CF)
- 1,262 towers, ~100,000 insulators, ~3,000,000 m of conductor
- Weight of steel required for towers and foundations ~ 15,000 tonnes
- Hvac line: 371 stream crossings


DC Transmission (Labrador-Island Link)

- ~ 1100 km of 350 kV DC TL (Muskrat Falls to Soldier's Pond)
- Engineered to withstand the harsh environmental and weather conditions experienced in Newfoundland and Labrador
- 3230 towers, ~330,000, ~2,184,000 m of conductor
- Weight of steel required for towers and foundations ~ 45,000 tonnes
- HVdc line: ~ 373 bridges (small to large) / ~900 culvert stream crossings
- ~ 1100 km new access roads, and ~ 800 kms upgrades to existing roads


Line routing





Long range mountains



Foundation installation



Tower erection



Stringing




Overview of components

Strait of Belle Isle Marine Crossing

Strait of Belle Isle Crossing

The Background




- The Strait of Belle Isle (SOBI) subsea cable crossing is the transmission component that connects Labrador to Newfoundland.
- High quality and reliability is an absolute requirement.
- In the early project phases, the SOBI crossing was one of the key project risks.

Strait of Belle Isle Cable Crossing


- 30km marine cable crossing connecting transmission line from Labrador to Newfoundland
- Three marine power cables along the seabed
- Using horizontal directional drilling (HDD) technology, drill rigs bored three holes from the shoreline and out under the seabed on both sides of the Straits to protect against iceberg scour and pack ice
- Cables placed along the sea floor and covered by protective rock berm
- Cables follow natural bathymetric lines, below depth of icebergs in the area

Risk of Iceberg Scour



Strait of Belle Isle Crossing

The 'Bathymetric Shield'




Strait of Belle Isle

SOBI Route Selection



Illustration of horizontal directional drilling



HDD Drilling at Forteau Point




Strait of Belle Isle Crossing – cable details

Cable Manufacturing



Batch 3 completion



+/-350 kV, 1300 mm² Cable



First cable on sea floor




Strait of Belle Isle – rock protection

Work during winters




Subsea rock protection



Rock protection loadout




Tideway Flintstone



Overview of components

HVdc specialties

HVdc specialties - scope



- **Three (3) HVac substations**
 - 735-315 kV Churchill Falls
 - 315 kV Muskkrat Falls
 - 230 kV Soldiers Pond
- **Two (2) HVdc converter stations**
 - ± 350 kV Muskkrat Falls
 - ± 350 kV Soldiers Pond
- **Two (2) HVdc transition compounds**
 - ± 350 kV Forteau Point
 - ± 350 kV Shoal Cove
- **Two (2) shore line grounding sites**
 - L'Anse au Diable
 - Dowden's Point
- **One (1) synchronous condenser facility**
 - 3 x 175 MVar Soldiers Pond
- **Other systems**
 - Telecommunications & system integration
 - Construction power

Muskrat Falls – switchyard & converter station

MF Switchyard & Converter Station



Converter Transformer (MF#3) – Converter Station



Gas insulated switchgear



Switchyard, Converter, & Synchronous Condenser



Muskrat Falls – synchronous condenser

Synchronous Condenser



Rotor Assembly



Stator Frame



Synchronous Condenser



Soldiers pond

Valve Installation Pole 1




DC Yard Gantry Erection



Equipment Installation




Conductor Stringing



735/315/13.8kV Power Transformers

10-Dec-2015



Dowden's Point

Grounding Station




Dowden's Point Construction



Lower Churchill Project Global Reach

Locations around the world where components for the Muskrat Falls Project are being manufactured and fabricated



Proven technology

Proven technology, no serial #1's and no scale-ups ensure operational integrity

MF	LTA	LIL
<ul style="list-style-type: none">• Low-head, no penstocks concrete powerhouse founded on Canadian Shield• Proven, model tested Kaplan turbines well within flow and head range• Design philosophies based on over 40 years of hydro-electric and transmission engineering, construction and operations• Conservative efficiency targets supported by equipment redundancy• Core Nalcor technology	<ul style="list-style-type: none">• Conventional AC technology• Extension of existing Labrador transmission system• Core Nalcor capability – existing lines up to 735 kv	<ul style="list-style-type: none">• LCC HVDC technology used in Canada for 40+ years• Mass impregnated submarine cables• SOBI cable protection methods proven offshore east coast• Typical HVdc overland transmission• Standard HDD technology well with the boundary of design for size and distance

Current project status

The overall project progress is ~90% as of April 2018

Project progress

	<u>Name</u>	<u>Approximate % Complete</u>	<u>Scope</u>
LTA (100%)	■ Valard	100%	T-line construction AC
	■ Grid Solutions	100%	CF/MF switchyards
LITL (99%)	■ Valard	100%	T-line construction DC
	■ Grid Solns/ Alstom Ren. Power	97%	Switchyards, converter stn., synchronous condensers
	■ Multiple	100%	Clearing and access
	■ Nexans	100%	Subsea cable
MFG (81%)	■ Astaldi	90%	Powerhouse, intake, and spillway, transition dams
	■ Andritz	75%	Turbines, generators, gates
	■ Barnard Pennecon	60%	Dams
	■ Cahill-Ganotec	20%	Balance of plant
	■ Gilbert	100%	North Spur stabilization
	■ Johnsons	100%	Reservoir clearing

1 Approximate Forecast Value (April 2018)

LOWER CHURCHILL PROJECT