

Nalcor Energy – Lower Churchill DG3 Capital Costs Overview

19-September-2012

Boundless Energy



Confidential and Commercially Sensitive

Safety Moment



Purpose / Objectives

- To present the Decision Gate 3 capital cost estimates.
- To review key drivers of Decision Gate 3 capital cost estimate.


Presentation Outline

- The Project Today
 - Project Execution Roadmap
 - Project Definition since Decision Gate 2
- Decision Gate 3 Cost Estimate
 - Process and Outcome
 - Review Key Changes since Decision Gate 2

Project Execution Roadmap

Application of Industry Best Practice


- Front-end loading to confirm project scope and align with business objectives
 - Advanced Project Definition through completion of substantial engineering
 - Target engineering completion prior to start of construction
 - Extensive execution and construction planning
 - Adopt contracting strategies that minimizes and optimally allocates risk
 - Firming key prices through bidding before Sanction
- Early and continued focus on de-risking the projects
 - Shaped engineering, execution planning, contracting strategies, and decision to commence Early Infrastructure Works



"... the LCP Gate 3 estimate in its current state is one of the best mega-project "base" estimates that this reviewer has seen in some time."

- John K. Hollmann, PE CCE CEP, Owner – Validation Estimating LLC
April 2012


Front-End Loading: *#1 Predictor of Performance*




- Gateway Phase 3 focus directed towards completing the level of Front-End Loading to confirm the project definition and a “Sanction-quality” Class 3 cost estimate.
- We are tracking industry best practice which suggest expending 4 – 6% of Total Invested Capital in FEL activities pre-DG3
 - ~\$250 million expended to-date
 - Engineering and detailed design well advanced > 45% complete

Nalcor's Stage-Gate Process

Structured, front-end loading process that enables risk-informed decision making at Decision Gates by completing critical analysis in the Phase leading to the Decision Gate, while ensuring a balance of analysis with capital pre-investment .



Project Milestones



Establishing a High Quality DG3 Cost Estimate


- Estimate accuracy is the degree of confidence that the estimated cost will be close to the final project cost.
- As a project becomes better defined and less likely to change the more confidence there is that the estimate will accurately predict the final project cost.
- The accuracy of a project's cost estimate is a function of the:
 - level of Front-End Loading (i.e. project definition) completed
 - understanding and completion of project's risk exposure

Estimate Accuracy

Shaping Characteristics for Lower Churchill

- Primary Driver:
 - High degree of project definition (i.e. represented by amount of engineering completed)
- Secondary Drivers:
 - Non-technically complex Project
 - Significant amount of effort expended to prepare estimate
 - High quality reference cost data available

Estimate Accuracy Evolution



Required for	Decision Gate 1	Decision Gate 2	Decision Gate 3	Financial Close	Mid-Point Check
Class	AACEI Class 5	AACEI Class 4	AACEI Class 3	AACEI Class 2	AACEI Class 1
Estimate Purpose	Opportunity Screening	Alternative Selection	Sanction / Control	Financing	Check Estimate
Project Definition	0% to 2%	1% to 15%	10% to 40%	30% to 70%	50% to 70%

Project Definition Since DG2

Significant Engineering has been completed since Decision Gate 2

- Followed work plan established at DG2 with early engineering directed towards areas of uncertainty
 - ~400 FTEs employed
 - Currently >45% engineering and detailed design complete – 1000+ document & drawings issued
- Project scope and execution plan have been confirmed, thereby allowing:
 - well-informed decision at DG3
 - more accurate cost estimate
 - matured risk awareness
 - enhanced capital predictability


Project Definition – HVdc Transmission

A Closer Look: HVdc Transmission

Significant Engineering Design Development Complete

DG2: Working with general knowledge of Corridor Only

Now: Individual Tower Locations Selected



HVdc Engineering & Design Progress

Decision Gate 2

- Preliminary 2km wide Transmission Corridor selected and basic geotechnical data obtained
- Generic tower configurations – not specific to our line
- Desktop tower loading work underway
- Preliminary execution plan
- Preliminary conductor selection
- Budgetary quotes for tower steel and conductor




Decision Gate 3

- Lidar topography survey complete of Corridor
- Line Routing within Corridor complete
- Individual tower locations selected
- Harsh climatic conditions of southern Labrador and Long Range Mountains confirmed with meteorological data and / or modelling
- 13 Tower loading cases identified resulting in significant number of tower designs
- Foundation designs in-progress
- Conductor Optimization and System Stability studies complete
- ROW vegetation and clearing plans in-place
- Insulator and tower hardware designs progressing
- Budgetary quotes for all material
- Detailed construction plan in-place
- Acquisition of property for Marshalling Yards underway
- All line crossings and property easements identified
- Tie-in points being design

Meteorological Conditions


- 3650 towers
- 350,000 Insulators
- 3,000,000 m of Conductor
- 13 distinct wind and ice combination zones developed from multiple desktop report and existing network of test towers/ test spans
- 170 km of High Alpine (Rime) Ice and Wind Loading, 180 km Heavy Glaze Ice
- 250 km of remote inaccessible line in central Labrador



Meteorological Loading Cases Confirmed


- 696 km from Shoal Cove to Soldiers Pond
- Long Range Mountains
- Avalon higher population density, more existing infrastructure
- 13 Meteorological loading cases (135mm Rime Ice and 180 km/h winds)

③	4b	Average Zone 2	12.5	50	Glaze	120	N	Coastal	40	F10
	4a	Average Zone 2	56.4	50	Glaze	120	N	Inland	300	F5
	5	HQSL High Alpine	18.9	110	Rime	150	N	Inland	500	F12
	6	Average Zone 2	72.6	50	Glaze	120	N	Inland	480	F5
	7a	LRM High Alpine	21.1	110	Rime	180	N	Inland	590	F6
	7b	LRM Extreme Alpine	7.1	135	Rime	180	N	Inland	630	F6
	7c	LRM High Alpine	12.8	110	Rime	180	N	Inland	600	F9
	8a	Average Zone 2	12.9	50	Glaze	120	N	Inland	550	F5
	8b	Average Zone 1	74.9	50	Glaze	105	N	Inland	490	F4
	9	Alpine	7.8	75	Glaze	130	N	Inland	430	F7
④	10	Average Zone 1	221.0	50	Glaze	105	N	Inland	380	F4
	11a	Eastern Zone	89.4	75	Glaze	130	N	Inland	280	F7
⑤	11b	Eastern Zone	88.8	75	Glaze	130	N	Coastal	210	F6



Confidential and Commercially Sensitive

Detailed Topography Mapped




Elevation ranges from 0m to 630m above MSL


Lidar Terrain Mapping

(Lidar = Aircraft based remote sensing technology to detect terrain conditions)

Avalon - Starting at Port Blandford, higher population density, more infrastructure and land use constraints.



Field Assessment of Terrain to Verify Line Routing




Long Range Mountains

Leveraging Technology to Assist with Wood Density Estimation




HVdc Tower Designs In-Place (315 kV Tower Type C Design Layout)




HVdc and HVac Transmission Construction Sequence


Construction Build Sequence - 2012




Construction Build Sequence - 2013




Construction Build Sequence - 2014




Construction Build Sequence - 2015



Construction Build Sequence - 2016




Construction Build Sequence - 2017




Project Definition – Muskrat Falls

Muskrat Falls Today



MF Engineering Work Plan from DG2



MF Engineering & Planning Progress

Decision Gate 2

- Desktop studies complete based upon early field work to confirm development Variant
- Quantities calculated using 1998 Feasibility Studies
- River and ice management studies underway
- 1998 geotechnical investigations
- Leverage Gull Island studies for infrastructure works




Decision Gate 3

- Numerical modeling of hydraulic passages complete
- Geotechnical investigations for powerhouse complete
- Site layout optimized to ensure operational reliability and long-term asset integrity
- All structures modeled in CATIA 3D to produce quantities of rock excavation and concrete
- Scaled physical model testing completed to verify layout and various river management operations (e.g. temporary diversion)
- Turbine efficiency model testing complete and incorporated into contractual commitments
- Detailed constructability optimizations complete / underway
- Turbine & Generator contract ready to award
- Engineering complete for infrastructure works

Geotechnical Investigations Confirm Sub-Surface Conditions

Borehole Locations at Muskrat Falls




Borehole Operations at Muskrat Falls





Numerical Modeling Identified Potential Operational Integrity Issues


- Hydraulic conditions near the surface upstream of the intake indicated the presence of eddies and flow velocity parallel to the intake at Unit 1 (at the top of the graph).
- These conditions indicate a possible problem at this unit, including the possibility of a vortex, increase of head losses at the intake or non-optimal flow conditions at the unit.



Solution: Plant Reorientation by 30°




Revised Layout Designed in 3D CAD




Design Optimization Continued

(Radial versus Vertical Spillway Gates)




Spillway – Assessing Downstream Erosion




Confidential and Commercially Sensitive

Layout Verified by Scaled Operational Model




Muskrat Falls Spillway

Numerical Modelling during PMF Event




Rare Operational Events Modelled (North RCC Dam – Secondary Spillway)




Video

3D Model used for Construction Planning (Superstructure under Construction)




Confidential and Commercially Sensitive

Powerhouse Cross-Section




Powerhouse Cranes (2 x 350 tons Working in Tandem)




Operational and Schedule Risk Reduction

Turbine Model Testing



Scroll Case



Runner Model (Diameter = 0.380m)

Draft Tube

Early Infrastructure Works (As of August 13, 2012)

MF Access Road Construction




Placing poles on 25 kV Line



Muskrat Falls Construction Sequence

2012 – December


Note: All Progress % are approximate




Confidential and Commercially Sensitive

50


2013 – September




2013 - December



2013 – December (Continued)




2014 - June



Confidential and Commercially Sensitive


2014 - December




Confidential and Commercially Sensitive

55

2014 – December (Continued)




2015 - June




Confidential and Commercially Sensitive

57


2015 – June (Continued)




2015 – June (Continued)




2015 - December




2015 – December (Continued)




2015 – December (Continued)




2015 – December (Continued)



2015 – December (Continued)




2016 – June




2016 – June (Continued)



2016 – June (Continued)




2016 – December




Confidential and Commercially Sensitive


2016 – December (Continued)



2017 – June (Continued)



2017 – June – First Power






Project Definition – SOBI Crossing


SOBI Crossing: A “deeper” look

Selected solution for the SOBI cable crossing builds upon team’s extensive experience in the design and installation of subsea infrastructure in harsh environments combined with learnings from global cable projects.


- Each of the 3 submarine cables will each have a dedicated horizontally directionally drilled (HDD) conduit to protect the cable from shore and pack ice at the landfall points.
- The conduits will take each cable to a water depth of between 60 to 80m, thus avoiding iceberg scour.
- The cables will then be laid on the sea bed and each protected with a separate rock berm which will protect against fishing gear and dropped objects




SOBI Iceberg and Pack Ice Protection



Conceptual Design Routing



Center Bank Extent




Nalcor's Estimating Approach

Nalcor's Estimating Approach

- Adopt industry recommended practice
 - Association for Advancement of Cost Engineering (AACE) International
- Focus on key cost drivers
- Fully engage project team
 - Combined Nalcor / SNC-Lavalin >400 FTEs
- Understand and apply lessons learnt from other projects
- Gather external and independent input

Cost Estimate Components




DG3 Estimate – How it was produced

- Owner-led estimate team comprised of SNC-Lavalin and various 3rd parties
- Developed over a 12-month period
- Leveraged extensive historical data for Hydro and Transmission projects developed in Canada
- Reflects what a construction contractor would need to do to evaluate project costs for which a bid is being prepared
 - This approach could be best described as a bottom-up first principle estimate as opposed to a parametric or stochastic method
- Concurrent “Check” or validation estimates and Estimate Process Check completed by expert consultants


Establishing the Cost Estimate

The accuracy of the cost estimate is a function of the engineering, procurement and contracting carried out as shown below




* Association for the Advancement of Cost Engineering International

The Estimators Consider 4 Elements



Estimate Leverages Extensive Information



Key Quantities

- Powerhouse, Intake and Spillway
 - Mass Excavation of 2.5M m3
 - 390,000 m3 of concrete
 - 200,000 m2 of formwork
 - 57,000 tonnes of rebar
 - 88m high and 225m wide (the Peace Tower is 92.2m high)
- Dams and Cofferdams
 - 895,000 m3 material
- Roller Compacted Concrete:
 - 226,000 m3 RCC
- North Spur:
 - Overburden and rock excavation of 700,00 m3
 - Rockfill of 1M m3
- HVac LTA Transmission
 - 490 km in length
 - 1280 towers
- HVdc LITL Transmission
 - 1079 km in length
 - 3642 towers
- MF Reservoir
 - 1,800 hectares
 - 157kms of roads
 - 390,000 m3 of merchantable wood

Third Party Validation

“... the LCP Gate 3 estimate in its current state is one of the best mega-project “base” estimates that this reviewer has seen in some time. My conclusion is that this is in large part due to the active involvement of the owner leads in striving for best practices and quality.”

John K. Hollmann, PE CCE CEP, Owner – Validation Estimating LLC

(Recipient of AACE’s highest honor, the Award of Merit, for editing/authoring the Total Cost Management Framework and authoring or assisting in developing many of AACE’s Recommended Practices)

Questions

Back-up Material

Wuskwatim Comparison

				EA Release Aboriginal Agreement signed Start of Construction				The forecast cost is 16% greater than the 2006 estimate
Year	2003	2004	2005	2006	2007	2008	2009	2011
Estimated Cost	\$0.99 B	\$1.04 B	\$1.14 B	\$1.35 B	\$1.59 B	\$1.59 B	\$1.59 B	\$1.57 B

- The 16% cost increase since start of construction is primarily driven by labor rates – Manitoba has a Province wide agreement on rates rather than Project specific labor agreements. The rates established had to be increased to attract and retain the trades required.
- Both Lower Mattagami (OPG Project) and Lower Churchill Project have learned from this and have estimated labor rates and site conditions which mitigate this risk.

Muskrat Falls Capital Cost is Driven by favorable Site Characteristics

Key Element	Muskrat Falls Site Characteristics
Geotechnical Conditions	<ul style="list-style-type: none"> • Competent bedrock (Canadian Shield) exposed / near surface • Minimal overburden to remove and dispose • Conditions validated by comprehensive site investigations, thus limited exposure with respect to quantity growth
Physical Layout	<ul style="list-style-type: none"> • No peripheral structures (i.e. dykes) required to create the Reservoir– basically “filling up the river valley”, leveraging Churchill Falls reservoir – no land purchase issues • Reliable and predictable flows leading to smaller variations in operating water levels • All power structures located at one main site • Simple / robust / conventional designs for major permanent structures (Intake , Powerhouse, Spillway, Aux. Dams) <ul style="list-style-type: none"> • Conventional or roller-compacted concrete founded on bedrock • Generally low-profile dam structures (30 to 40 m high) • No underground works (MF has surface powerhouse) • No temporary spillway facilities to be constructed • Diversion uses existing topography and permanent structures (i.e. Spillway) rather than expensive temporary structures (e.g. Diversion Tunnels) • Conventional equipment (T&G sets, gates, cranes) • Access by road from Trans-Labrador Highway
Constructability	<ul style="list-style-type: none"> • All construction materials primarily sourced from site excavations • Very good material balance leading to minimal excess material / spoils • Mostly conventional concreting methods and equipment, in dry conditions